



ADDENDUM NO. 2

Project: Montana State Hospital – Lagoon Cleanout and Restoration

Owner: State of Montana

Engineer: Anderson-Montgomery Consulting Engineers
1064 N. Warren
Helena, MT 59601

Date of Addendum: February 18th, 2025

Bid Opening Date: February 20th, 2025 at 2:00 p.m.

The following corrections, clarifications, and/or alterations to the specifications for the project are as such a part and parcel of said plans and specifications as if included therein.

Modification to Language in Specification (~~stricken~~ language removed, **bold underline** language inserted):

CLARIFICATION:

1. Question: Contractor asked about the quantities of sludge in the Cells referencing specification 46 06 70.

ANSWER:

Division 46, Section 46 06 70 – Sludge Handling & Disposal, Section 1.02 B. 1.


Sludge quality and quantity data is based on measurements taken in August 2018 and August 2024. The estimated volume of wet (in place) sludge within Cell #2 including the sludge from Cell #1 is ~~1,985 yd³~~ **26,417 yd³** (712 dry tons) (with approximately 42.6% total solids. The estimated volume of wet (in place) sludge within Cell #3 is ~~960 yd³~~ **9,913 yd³** (426 dry tons) with approximately 52.8% total solids. Considerable reduction in sludge volume can be expected if the material is dried to a higher solids content through a freeze/thaw cycle.

Please Remember To Note Receipt Of This Addendum On The Bid Form. Failure To Do So Will Result In Disqualification.

**Issued By: ANDERSON-MONTGOMERY, 1064 N. WARREN, HELENA, MT 59601,
Adam Eckhart, P.E., Project Manager**

Office: (406)-449-3303, Fax (406)-449-3304

Adam@a-mce.com



END OF ADDENDUM NO. 2